

# Assessment of Road Project for Accelerating Permanent Connectivity

Dipak Basnyat<sup>1\*</sup>, Buddhi Raj Joshi<sup>2</sup>

<sup>1</sup>Consultant Engineer, Infrastructure Development Office, Pokhara Metropolitan City-17, Kaski, Nepal

<sup>2</sup>Lecturer, School of Engineering, Pokhara University, Pokhara Metropolitan City-30, Kaski, Nepal

DOI: [10.36348/sjet.2020.v05i01.001](https://doi.org/10.36348/sjet.2020.v05i01.001)

| Received: 16.01.2020 | Accepted: 23.01.2020 | Published: 30.01.2020

\*Corresponding author: Dipak Basnyat

## Abstract

Performance Assessment is the tools which give clear indication about the construction status of the project which finds out the strength and weakness of project implementation and examines the effectiveness of technical social and environmental parameters of the Road construction project. Strengthening the National Rural Transport program (SNRTP) is introduce to fulfill the aim of GON to provide all-weather road access to all Village Development Committee (VDC) by gradually upgrading the District Road Core Network (DRCN) and providing proper maintenance. Assessment of the project's measured the project output, budget, time deadlines, quality, deliverables, and specifications. The study was focus on finding out different stage, parameters, process used in road construction project and checking compliance of Technical, social and environmental parameters with prescribed design standard. Geometric parameters, road safety and maintenance, bio- engineering and plantation works, implementation on VCDP and GAP was not found as per requirements. Project was completed 18 months behind the original completion date so the project management has failure to control the time overrun.

**Keywords:** Road Project, Permanent Connectivity, (SNRTP), District Road Core Network (DRCN).

**Copyright @ 2020:** This is an open-access article distributed under the terms of the Creative Commons Attribution license which permits unrestricted use, distribution, and reproduction in any medium for non-commercial use (NonCommercial, or CC-BY-NC) provided the original author and source are credited.

## INTRODUCTION

### Background

Assessment of the project is the process of analyzing the actual, as against the projected estimates in respect of time, cost and quality specifications. Assessment includes investigation of the variances per constituent of the project objectives (and, within such constituent, major elements of variances) leading to the assessment of the overall situation. Project assessment are effective in disseminating knowledge about good practices, correcting errors in individuals' knowledge (especially their knowledge about other functions within the organization), and predicting how well alternative practices would have turned out. At the same time these reviews demonstrated several limitations. The diagnosis that took place in reviews tended to be shallow, remedies was planned only at a very superficial level, and explanations of events tended to be overly specific. Participants also made potentially misleading assumptions: for example, those unimportant problems implied unimportant causes. Nonetheless, post-project reviews are important learning mechanisms and their value seems to be underestimated by individuals who do not appreciate the need to disseminate insights throughout the organization. Project assessment gives clear indication

about the construction status of the project it finds out the strength and weakness of project implementation. The project assessment is somewhat like a lessons learned activity which provides great information to practice on future project engagements. Assessment of the project's measured the project plan, budget, time deadlines, quality, deliverables, specifications, and client satisfaction. Performance assessment of Road consists of checking compliance and noncompliance of different Components of Road project.

### SNRTP Project

At the end of the Fiscal year 2068/69(2011/2012), Nepal had 50,944 km of rural roads [1]. Two-thirds of rural roads are earthen and remain inaccessible during the rainy season. Blacktopped and graveled roads are poorly maintained, further affecting access. The rural transport infrastructure has been attracting around 6% of national budget (NPR 26 billion in 2011/12) which will be increasing over the years. The importance of local governments in promoting sustainable development of rural roads is being felt seriously [2]. So SNRTP project was introduce to fulfill the objective. The Government of Nepal (GON) aims to provide all-

weather road access to all VDCs by gradually upgrading the District Road Core Network (DRCN) and providing proper maintenance with the aim of promoting economic growth, providing access to services and creating sustainable decent jobs in rural areas. Currently a large majority of roads are only fair-weather and in poor condition, with a large portion of roads not trafficable. Insufficient maintenance is being carried out, further aggravating the situation. In this context, GON with support of the World Bank is implementing the SNRTP project to strengthen the DRCN with a particular emphasis on the "Maintenance First" approach. This project will furthermore cover the upgrading and rehabilitation of rural roads as well as the construction of new river crossing structures to bring the roads to an all-weather maintainable standard. The project covered 36 districts with the total population of more than 14.6 million people [3].

### Objectives of the Project

- The Project Development Objective (PDO) for this project is to enhance the availability and reliability of transport connectivity for rural communities in the participating districts.

- Project outcomes include (i) increased access to all weather transport connectivity for communities in participating districts; and (ii) improved reliability of rural transport infrastructure in participating districts [2].

### Project Component

#### Component A: Institutional Strengthening and Technical Assistance

Component A will fund three categories of activities including: (A1) institutional strengthening and technical assistance; (A2) beneficiary monitoring of physical works under Component B of the project; and (A3) an impact study of selected project interventions.

#### Component B: Maintenance Upgrading and Rehabilitation

Component B will support districts to implement physical works through two funding windows: (B1) output-based maintenance of rural transport infrastructure; and (B2) upgrading or rehabilitating rural transport infrastructure.

### SNRTP Financing

Funding source	Amount (USD million)	Percentage
World Bank IDA Grant	\$72.00	41.0%
World Bank IDA Credit	\$28.00	16.0%
GON funding	\$75.40	43.0%
Total	\$175.40	100.0%

Financing of SNRTP Project [2]

## OBJECTIVE OF THE STUDY

The objectives of the study are as follow

- To assess compliance with technical, environmental and social parameter.
- To identify the gap between design and implementation of the project, recommendation for future improvement and best practices of the project.

### Significance of the study

The study will critically analyze the Technical, Social and Environmental parameters for the project effectiveness after the construction of road. Identification and description of Different Technical, Social and Environmental parameters helps the fresh technical person and entrepreneur who are interested in road construction field. SNRTP project set the certain Guidelines for successfully completion of the project. From this study it will be easy to find out whether the project components were compliance or non-compliance with the approved guidelines. This study will also be helpful for concern stakeholders to know actual condition of the sub-project after the completion of the project. This Study methodology will help other similar project for performance Assessment.

### Limitation of the study

- SNRTP Syangja has complete three road sub project Walling-Dumrebhanjyang, Rangkhola-Biruwa and Badkhola-Takshar. All this three project has same nature, the starting date, completion date, time extension, Variation order are same and exist on same day also. So my study covers one road projects (Badkhola-Takshar-Delegaunda).
- Planning and budgeting section of project was not included in the study.
- Laboratory testing was not carried out for quality measurement.

## LITERATURE REVIEW

### General

"Managing Roads for National Integration and Socio-Economic Development" is the vision for development of roads in Nepal. The transport sector in Nepal is dominated by the road transport which accounts for almost all domestic passenger and freight movements [4].

Road network in Nepal is divided into Central Road System and Local Road System as per the National Transport Policy of the country. The Strategic Road Network (SRN) as per Department of Roads (DoR) classification is a part of the Central Road System which also includes the Asian Highway. This System is administered by the Ministry of Physical Infrastructure and Transport (MoPIT) and the implementing agency is DoR. The mission statement for the Department of Roads is "To contribute towards the betterment of living conditions of the people through effective, efficient, safe and reliable strategic road connectivity". In addition to the extension of strategic network, a considerable expansion of the local rural road network has occurred over the past 10 years, the construction of such being undertaken by a larger number of local initiatives and agencies often involving

significant local participation [4]. Assessment of the project represents evaluation of the project after its completion, analyzing the actual, as against the projected estimates in respect of time, cost and quality specifications. The evaluation includes investigation of the variances per constituent of the project objectives (and, within such constituent, major elements of variances) leading to the assessment of the overall situation. Project evaluation is a systematic and objective assessment of an on-going or completed project. The aim is to determine the relevance and level of achievement of project objectives, development effectiveness, efficiency, impact and sustainability. Evaluations also feed lessons learned into the decision-making process of the project stakeholders, including donors and national partners.

**Table-1: Evaluation method from literature review [5]**

Researchers	List of Indicators and Evaluation Method
Tabish and Jha [7]	Overall success : Nine-point scale
	Anti-corruption norms: Nine-point scale
	Financial norms: Nine-point scale
Shahrzad Khosravi [8]	Time Performance
	Cost Performance
	Quality Performance
	Client Satisfaction
Al-Tmeemy <i>et al.</i> [9]	Quality Targets
	Schedule
	Budget achievement
	Satisfaction of customer
	Functionality
	Meeting specification
	Profit achievement
	Market development
	Reputation
Ahadzie <i>et al.</i> [10]	Competitive Improvement
	Project Cost
	Project duration
	Project Quality
	Customer Satisfaction
	Environmental impact
Menches and Hanna [11]	Profit (0.583)
	Realistic schedule (0.033): How realistic: 1-5
	Communication (0.133): Rate how good: 1-5
	Achieved budget cost (0.083): Exceed or not: Y/N
Bryde and Robinso [12]	Project Cost (*)
	Project Duration (*)
	Technical specification
	Customer Satisfaction
	Stakeholders Satisfaction (*)
Chan and Chan [6]	Time: Construction duration, Construction speed, Schedule variation
	Project cost: unit
	Profit: net present value
	Safety: Accident rate, EIA or ISO 14000
	Environmental performance: Number of complaints
	Quality: Seven-point scale
	Functionality: Seven-point scale

### Quality Assurance Plan (QAP)

Quality Assurance (QA) means a process for assuring the reliability of measurement data. QA principles and practices enable you to acquire data of the type and quality you need. The quality of the data must be documented in order to be scientifically and legally defensible. The purpose of preparing the QA Project Plan is to ensure that all necessary steps are taken to acquire data of the type and quality needed. A project or study is a logical sequence of activities grouped into three categories:

#### Planning → Implementation → Assessment

QA Project Plan documents the planning phase and guides implementation and assessment. A QA Plan are Lists the goals and objectives of a study; Identifies the type and quality of data needed; Describes the sampling and measurement procedures needed to acquire those data and Describes the QC and assessment procedures needed to ensure that the study objectives are met [13].

### Extention of time (EOT)

Delays in construction activities may give rise to a need for an application of extension of time, to provide sufficient time to complete the project. Most standard form of contract contain provisions that list out relevant events that allow a contractor to apply time extensions; the contract often expressly states that the claim should be made and dealt with timely as possible with the delaying events. Unfortunately, no specific explanation with regards to the assessment of the claim is given, and this is left to the professionals involved in the project. Often, interpretation varies depending on the experience and preference of the individual party. The absence of clear guidelines and mutual agreement between parties involved regarding the assessment of construction delay will sometimes sparks a dispute amongst them [14].

In SNRTP Project, The Project Manager shall decide whether and by how much to extend the Intended Completion Date within 21 days of the Contractor asking the Project Manager for a decision upon the effect of a Compensation Event or Variation and submitting full supporting information at least 7 days prior to the intended completion date. If the Contractor has failed to give early warning of a delay or has failed to cooperate in dealing with a delay, the delay by this failure shall not be considered in assessing the new Intended Completion Date.

### Variation Order (VO)

The cost of a construction project is one of the most important factors in the construction industry. Due to many reasons, the total cost of a project can significantly vary from the initial estimated cost. The reasons could be changes in scope of work, specifications, or any other contract documents. In the construction industry, variation orders are created when

changes occur. It is an official document that states the changes made into the original agreement between the client and the contractor. When a variation order is created, it brings several negative effects to both the client and the contractor [14].

### Liquidated damage (LD)

In a construction context, delay liquidated damages (LDs) typically represent an agreed, fixed amount (usually a daily or weekly rate) payable by a contractor to the employer in circumstances where the contractor fails to complete the work under the contract by the date for completion specified in the contract (being either the original date for completion, or where the date has been extended in accordance with the contract, the extended date for completion). It is not unusual for the total amount of LDs to be capped at a percentage of the contract price.

The following are commonly cited as a few of the benefits to the parties in agreeing a rate of LDs as part of their contract:

It quantifies the risk of late completion and permits a contractor to properly consider the risk at the tender stage; it provides the parties with certainty; it removes the need for the employer to prove the actual damage suffered [15].

In SNRTP project the liquidated damages for the whole of the Works are 0.05 PERCENT of the final Contract Price per day and that for the Milestones is as under;

Milestone 1: 0.005% of Contract Price per day,  
Milestone 2: 0.025% of Contract Price per day and  
Milestone 3: 0.05% of Contract Price per day.

Liquidated damage for Milestone 1 will be levied until end of Milestone 2, and then only liquidated damage of Milestone 2 will be levied until end of Milestone 3, and so on. No Two liquidated damage will be applicable at one time. The maximum amount of liquidated damages for the whole Works is Ten (10) percent of Contract price.

### Price Adjustment

Price adjustment is a modification made to the overall price of a contract to take account of legitimate changes in the costs of performing the contract. It is a mechanism to protect both buyers and sellers from unforeseeable input price fluctuations. This guidance note discusses price adjustment provisions for goods, works, and plant contracts. Price adjustment provisions are planned during the procurement planning and bid preparation stages. Price adjustment provisions are meant to give protection to the contractor against price escalation. Cumulative impacts of price escalation can be substantial in contracts with long delivery and completion periods. Contracts that include large, price-

sensitive materials or commodities can also experience abrupt and significant increases in price. Price adjustment may also pass on savings to the borrower (or grant recipient) due to the downward movements in price. ADB applies a general guidance that any contract with a delivery or completion period beyond 18 months should contain an appropriate price adjustment clause. The price of some components may still vary significantly within time periods shorter than 18 months. These usually include bitumen, fuel, cement, reinforced steel, etc. Where the price of such components fluctuates over short periods of time, it is also appropriate to include a price adjustment clause, whatever the length of the contract [16].

### **Defects liability period (DLP)**

Construction contracts usually include a defects liability period during which the Contractor is responsible for repairing or rectifying defects that appear in the works. The period usually commences upon practical completion of the works and runs for a specified time frame (sometimes also known as the Maintenance period). Under a construction contract, one of the Contractor's primary obligations is to carry out and complete the works to the standard set out in the contract. The defects liability period is intended to complement this liability by setting out how and when the Contractor must remedy defective work which becomes apparent during the defects liability period. In effect, the defects liability obligation recognizes that defects will arise in the period following completion and includes the obligation to repair those defects in the general obligation to complete the works to the required standard. The defects liability period provides a practical mechanism to the Employer for the repair or making good of defects which may not be apparent before completion, without resorting to dispute resolution. Making the Contractor responsible for carrying out the repairs is usually cheaper and more efficient than either the Employer repairing the defect itself or engaging a third party to repair the defect [17].

### **Environment Management Plan (EMP)**

By nature of the physical activities, road constructions bring about changes in natural environment and therefore, are considered environmentally sensitive. SNRTP intends to reduce environmental problems arising from such intervention to as minimum extent as is possible. Regardless of outcome of environmental screening, each subproject shall have its site specific EMP. Therefore, all subprojects will have their site specific EMP prepared for construction, upgrading and maintenance, during detail engineering design period [18].

### **Vulnerable Community Development Plan (VCDP)**

Vulnerable Community Development Plan (VCDP) will be prepared for the betterment of vulnerable people. The targeted beneficiaries of VCDP include mainly the following groups of people.

Severely Project Affected Persons/ Families, Marginalized groups such as indigenous community (janjati / adivasi), dalits, ethnic minorities and poorest people, Single women/ women headed households, and Landless, old aged and disabled people. The VCDP will identify the needs and priority of indigenous community and other vulnerable groups and proposes need-based programs to uplift their socioeconomic condition through appropriate training and skill transfer [1].

### **Voluntary Donation Impact Mitigation Plan (VDIMP)**

Based on the findings of the Social screening report, the subproject specific Voluntary Donation Impact Mitigation Plans (VDIMP) will be prepared to address impacts associated with donation irrespective of the type and scale of impacts that could arise in various forms: (i) loss of land; (ii) loss of houses /structures; (iii) loss of livelihood systems/income sources; and (iv) loss of community property resources. The VDIMP presents total land of the donors, donated land and its percentage, percentage of structural damage and loss or disturbance in income source and common community property. Moreover, it presents category of land donors as less than 10 % land donors, above 10% land donors whose remaining holding is above 1693 Sqm, in between 850 to 1692 Sqm and below 849 Sqm. The VDIMP will also suggest cost effective mitigation measures, required budget as per Entitlement Matrix and detail time frame to implement all activities starting from the beginning to land ownership transfer [1].

### **Voluntary Donation Impact Mitigation Fund (VDIMF)**

Although the Government of Nepal acquires the land as per the Land Acquisition Act for the national level projects, SNRTP will pursue the principles of limited voluntary land acquisition from owners who will be provided with some cash assistance as incentive in lieu of their contribution. In response to GoN policies of guarantying property rights and World Bank social safeguard policies, the project has devised the VDIMP to ensure some cash assistance and rehabilitation supports to project affected people of various categories even if the impacts are marginal as a result of voluntary donation. Three percent of total project cost will be contributed by the project for this fund [1].

### **Gender Action Plan (GAP)**

Although females are identified as vulnerable groups and included amongst the potential beneficiaries under the vulnerable plan, this alone does not suffice to address the deep rooted social, cultural and economic issues of females. Regardless of caste and ethnicities, females in general, suffer more than their male counterparts on various grounds warranting special treatment or mitigation measures in order to be able to sustain better livelihood. The social screening and consultations will help in

generating information, about the issues and concerns of men and women in sub-project areas which will help project to prepare a full-fledged Gender Action Plan (GAP) [1].

### Occupational Safety and Health (OSH)

“Occupational Safety “means the freedom from unacceptable risk of personal harm from, or in relation to, employment, i.e. the avoidance of accidents and incidents during the time of employment and working hours. “Occupational health” means the physical and mental wellbeing of a person and the freedom from any illness caused from, or in relation to, working conditions during the time of employment and working hours [3]. All workers and supervisory staff when on any site shall wear the basic safety clothing specified. Where additional safety equipment is required by nature of the site, then all workers and supervisory staff when on any part of that site shall use the additional equipment in addition to the basic safety clothing specified.

### Provision and standard of different items of work

#### Sub-grade

The sub-grade is top 300 mm compacted layers in embankment or cutting just beneath the

pavement crust. The sub-grade in embankment is compacted to a higher standard than the lower layers of the embankment. In cutting, the cut formation, which serves as the sub-grade, is treated similarly to achieve the specified density to provide a suitable foundation for the pavement [19].

#### Sub-Base

The material to be used for such works shall be any individual or combination of naturally occurring mechanically stable quartzite gravels, river gravels and transported gravels, or granular materials resulting from the weathering of rocks, clayey silty sand etc depending upon the approved quality and the grading. The material shall be free from organic or undesirable substances.

The grading of the material after placing and compaction shall be a smooth curve within and approximately parallel to the envelope given in Table 3 –1(a).

The Plasticity Index shall not exceed 6%.for sub base and shall be in the range of 6-12% for uncovered gravel layer [19].

**Table-2: Grading envelope for granular sub-base materials**

Sieve Size (mm)	Percentage by Weight Passing the Sieve
63.0	100
40.0	70-100
20.0	50-85
10.0	40-75
4.75	30-60
2.36	20-45
1.18	15-35
0.075	4-15

#### Crusher Run Material (CRM) Base

The base material for this purpose shall be crusher-run material from an approved source. The source may be as-dug materials from a hill side, or river bed gravel, or a rock quarry or alluvial plain fields. The material from the approved source shall be run from the crusher to before getting approval for the use as Crusher Run Material (CRM) [1].

#### Grading

The grading of the material after placing and compaction shall be within and approximately parallel to the envelope given in Table 2.3. To determine the specific grading requirements, tests shall be conducted before and after the material has been mixed and spread out.

**Table-3: Grading envelope for crusher run material**

Sieve Size ( mm )	% Passing by Weight
50	100
40	75– 100
31.5	42-75
20	25-60
10	15-45
4.75	12-37
2.36	6-25
0.6	5-12
0.075	3-12

### Otta Seal

Otta seal consist essentially of a 16-30 mm thick bituminous surfacing constituted of an admixture of graded aggregate ranging from natural gravel to crushed rock in combination with relatively soft (Low viscosity) binders with or without sand seal cover. This type of surfacing contrasts the single sized crushed

aggregate and relatively hard (High viscosity) binders used in conventional surface dressing e.g. chip seals.

### Binder spray rates

The binder) spray rates in hot condition for un-primed base/sub-base course shall be as per Table 4 – 9(h) below

**Table-4: Bituminous binder spray rate**

Grading Type of Otta Seal		Open	Medium	Dense	
				AADT < 100	AADT > 100
Double	1 <sup>st</sup> layer ( * )	1.6	1.7	1.8	1.7
	2 <sup>nd</sup> layer ( * )	1.5	1.6	2.0	1.9
Single, with a sand cover seal	Crusher dust or coarse river sand	0.9	0.8		0.7
	1 <sup>st</sup> layer ( * )	1.6	1.7	2.0	1.9
Single ( * )		1.7	1.8	2.0	1.9
Maintenance	reseal(single)	1.5	1.6	1.8	1.7

### Sand Seal

The Materials, method of construction and requirements are for the construction of sand seal. A sand seal means an application of bituminous binder covered with aggregates as specified hereunder. The binder shall be a medium-curing cut-back MC-800 or MC-3000 or K1-60 cationic emulsion as specified in the Bill of Quantities. The aggregate shall consist of sand, or fine screenings free from organic matter, clay and other deleterious materials. The fines (passing a 0.425 mm sieve) shall be non-plastic. The grading shall be as specified in the Table 4 –8(a).

**Table-5: Grading of Aggregate**

Sieve (mm)	Percentage passing by weight
10.00	100
4.75	70-90
2.36	45-70
0.60	15-35
0.15	0-2

The rate of spray of binder shall be 1.4 Lit/m<sup>2</sup> for MC 3000 cut-back bitumen and 1.6 Lit/m<sup>2</sup> for Emulsion, 60% cationic. The rate of spread of the fine aggregate shall be 13 – 19 kg/ m<sup>2</sup>. [18]

### Relevant Policies of Government of Nepal

Public Road Act, 1974: The Act prohibits the construction of permanent structures (buildings) within road Right of Way (RoW). If road projects temporarily require land and/or other properties during construction, rehabilitation and maintenance, compensation is determined by the Chief District Officer (CDO). Provisions are also detailed for compensation for the extraction of construction materials.

Environmental Protection Act, 1997 and Environmental Protection Regulations, 1997: According to the EPA 1997, all development projects, including roads, should first be screened using criteria that are based on project type, size, location and cost, stipulated in the Regulation to determine the level of environmental assessment required (whether IEE or EIA or none). Usually, small projects such as rehabilitation of rural roads are not expected to cause significant environmental damage and require only minor environmental assessment.

Forest Act, 1993 and Forest Regulation, 1995: The road projects need to comply with the provisions of forest Act and Regulation when it requires the use of forestland for road construction/improvements. Clause number 68 (1) allows implementation of development project of national priority in forested area, if it does not pose significant adverse impact to environment and if there are no other alternatives, after approval of government (District Forest Office - DFO) and local forest authority (eg; Community Forestry User Groups).

National Park and Wildlife Conservation Act, 1972: This act prohibits any action that could be damaging to the park including; cutting of trees and other plants, any kind of residential structures, quarrying of materials, change in watercourse, etc. Activities prohibited in protected areas includes; hunting, damage or removal of forest products, grazing, mining, digging earth or any other similar material, block or divert river systems flowing through the park, construction or possession of house, huts or other structures,. Any intervention within National Park and Wildlife Conservation Area requires permission from Ministry of Forest, Soil and Water Conservation after recommendation from Department of National Parks and Wildlife Conservation.

Land Acquisition Act, 1977 and Land Acquisition Regulations, 1969: The Land Acquisition Act 1977 and the Land Acquisition Regulation 1969 clearly outline the procedures of land acquisition and compensation for public purposes. The act states that, if the government has already used the land for public purposes in the agreement of land owner then it is not required to follow acquisition process but can determine compensation as per the act (Section 26). Section 27 of the act clearly states that land for public purposes can be acquired through negotiation and in such case procedure laid down by the act do not have to be followed. Therefore, section 26 and 27 are applicable for obtaining land for the project.

Soil and Watershed Conservation Act, 1982: For the conservation and management of watersheds of Nepal, the Soil and Watershed Conservation Act, 1982 was enacted. Construct and maintain dam, embankment, terrace improvements, diversion channels and retaining walls; Under Section 10 of the Act, Watershed Conservation Officer has authority to grant permission to construct dams, drainage ditches, canals, cut privately owned trees, excavate sand, boulders and soil, discharge solid waste, and establish industry or residential areas within any protected watershed.

Labour Act, 2048 (1992) (first Amendment, 15 Magh 2054/ Jan.28, 1998): This Act in chapter -5 describes the Provisions Relating to Health and Safety of labours that a proprietor shall make to his employee. The Proprietor shall make the arrangements of clean and healthy working environment, arrangements of necessary preventive personal devices for protection of health from adverse any other source, to make provisions for sufficient supply of pure potable water during the working hours, to make provisions for separate toilets for male and female workers or employees at convenient place; necessary protective means shall have to be arranged for the protection of eyes and other organs of the workers and employees from injuries likely to be caused by dust or pieces while working in the Enterprise.

Child Labor (Prohibition and Regulation) Act, 2056 B.S. (June21, 2000 A.D.): This Act prohibits engaging child labour (below 16 years) in factory, mines and other risky works. This act along with others defines the construction enterprises as one of risky works.

Labour Rules, 2050 (1993): In chapter-3 of this rule describes that there will be no discrimination in remuneration to male or female worker or employee for engaging them in the works of the same nature of functions. This chapter also dictates regarding provision of compensation against injury, Compensation in case of grievous hurt resulting in physical disability, Compensation in case of death of any workers/ or employee.

## RESEARCH METHODOLOGY

### Methodology

Everyone uses information to make decisions about the future. If the information is accurate, there is a high probability of making a good decision. However, if the information is inaccurate, our ability to make a correct decision is diminished. It is true that better information leads to better decision. Information can be either primary or secondary. Primary data refers to information collected for the specific purpose at hand. On the other hand, secondary data refers to information that already exists to be used for another purpose. In the course of our research, we have made use of both primary and secondary data. Secondary data has been in the form of books, journals and articles from the internet. Our measuring instrument to assess primary data is field data verification. There are different ways to get primary information. Some of them are: personal questionnaires, talking with people, telephone surveys, E-mail and internet surveys, experiments, focus groups, observation among others.

### Study area

Badkhola Takshar-Dulegaunda road of SNRTP sub-projects in Syangja district is the study area of my research.




Fig-1: Location Map of SNRTP sub-project

Syangja District is located in Gandaki Zone of the Western Development Region of Nepal. It borders with Tanahu district to the East, Gulmi and Palpa districts to the West, Parbat and Kaski districts to the North, and Palpa district to the South. The district headquarter is Putalibazar, located at an altitude of 850 m. The district has 9 Rural Municipality and 4 Municipality. The total land area of the district is about 1164 square kilometre within latitude 27°52'N to 28°13'N and longitude 83°27'E to 84°46'E. Syangja district has an estimated road network of 1095

Kilometre, including 105.94 km of Strategic Roads managed by DOR and 443.36 km of District Core Road Network managed by Syangja DDC and 546.04 km of village roads managed by the VDCs. The District Core Road Network (DRCN) consists of a total of 38 district roads with a total length of 443.36 Km. Out of this total length there is 10.5% black topped, 7% gravelled and 82.5% earthen road surface. In terms of road serviceability there is only 17.58% of road length is all weather and remaining 82.42% of road length is fair-weather.




Fig-2: Study area of Badkhola-Takshar Road (Source: Google map, 2018)

The Badkhola-Takshar Road having total length 20.6 KM starting from Badkhola bazar to Kaule. Badkhola-Taksar-Dulegaunda road is the part of the road connecting Badkhola bazaar at Putalibazaar Municipality of Syangja district link from Siddhartha Highway. The section is starts from Devisthan (Ch: 8+000, Putalibazaar Municipality ) and ends at Taksar ,kaule settalement (Ch 18+000, Putalibazaar Municipality )The DTMP code of this road is (39DR030). Total length of this section is 10.00 km. The passing settlements are: Devisthan, Dhadhkelne, Thuladihi, Govinde Bhanjyang, Kaule, Taksar.

The socio-economic condition is Moderate in the sub-project area. Most of the people depend on agriculture. A few are engaged in the labor, services and small business activities. There are some small market centers in some part of the corridor. Around 13,796 populations reside along the subproject zone of influence. Brahman, Chhetri, Magar, Gurung and Dalit have occupied most of land.

## DATA COLLECTION

The data was collected through primary and secondary data collection method.

### Primary Data

The primary data are collected through mainly two methods:

- Field survey and observation
- Recorded documents.

### Field Survey and observation

From the field survey of total 10 KM road starting from Devisthan (CH 8+000) to Kaule (18+000) following data is observed:

The Road Gradient; Radius of Curve; Carriageway; Super elevation; Retaining structures; Pavement condition; Crossing structure; Bio engineering and plantation works; Quarry site and tipping site management and Road safety and maintenance status.

### RECORDED DOCUMENTS

Documents recorded in district technical office syangja from starting to completion phase of the project are collected. They are:

The Procurement document; Survey design and drawing; Lab test report; Quality assurance plan; Letter issued and forward during construction period; Environment and social report; Field visit report; VO and EOT documents and Payment Certificates.

## Secondary Data

Secondary data are collected through Different project documents, Journal, Books etc. that are: The DOR Norms and Specification; DOLIDAR Norms and Specification; Nepal Road Standard 2070; SNRTP Project operation Manual (POM); Project Appraisal Documents (PAD); Environment and social Management Framework (ESMF) and Quality Control Handbook for Rural Road Construction and Maintenance (Volume II).

## DATA ANALYSIS

From the data collected from primary and secondary sources, are divided into three parameters. They are (i) Technical Parameters; (ii) Social Parameters and (iii) Environmental Parameters.

Details analysis of above parameters was done by comparing these parameters into project guidelines

and specification. Technical parameters was compared with Project operation manual published by SNRTP project and standard specification of DOR and Social and Environmental parameters was compared with Environmental and social management framework (ESMF) published by SNRTP project.

After Analysis of different parameters of the project, critical review of all these parameters was done from Expert (Client, consultant, Contractor and concern stakeholders) and score given to each and every parameter of the project. For scoring separate sheet was distributed to the expert where different parameters of the project are include and score range is specified from 0-10. Spider charts is used to visualize graphically the project performance. Excel spreadsheet is commonly used for developing the charts, which plot the values of each performance indicator along a separate axis.

**Table-6: Assessment Parameters and evaluation criteria**

S.N	Parameters	Score
1	Technical parameters	10
2	Social Parameters	10
3	Environmental Parameters	10
Evaluation Criteria		Level of Evaluation
Poor		less than 2
Marginal		2-4
Satisfactory		4-6
Good		6-8
Very Good		Greater than 8

## CHAPTER 4: RESULT AND DISCUSSION INTRODUCTION

This chapter presents the detail assessment of technical, environmental and social parameters of the project. Compliance with these parameters was verified from project document analysis and field verification. After Analysis of parameters, critical review were done from Expert (Client, consultant, Contractor) and score will be given to each and every parameter and finally Spider charts was drawn to visualize the project performance.

### Salient feature of the project

The name of the Sub Project is Badhkhola-Taksar-Dulegaunda Road of Syangja District of Nepal. Total Length with Chainage is 22.40 km (0+000-22+400). The Proposed Length with Chainage is 10 km (8+000-18+000). The Covered VDCs/municipality and Settlement are Putalibazar Municipality, Devasthan, Govinde Bhanjyang, Dhadkhelne, Thuladihi, Taksar, Kaule settlement, Land use feature along the stretch cultivated land & Settlements. DTMP/DRCN Code 39DR030, Contract Identification Number: SNRTP-SYA-W-NCB-28.01-UG-070-071, Major Work/major intervention. The road improvement work includes horizontal curve improvement; embankment construction, water management and drainage

improvement; otta seal with sand seal cover and other EMP works, DPR Approval Date 2070/03/10(24-June, 2013), Approved Cost Estimate NPR 76,641,703, No objection on Bid Document is made on 2070/10/06(20-Jan-2014), Bid Notice Publication Date 2070/10/13(27-Jan-2014) in Nagarik Daily, Bid Opening Date 2070/11/14(26-Feb 2014), Bid evaluation finalisation Date is 2071/01/04(17-April-2014), Name of Contractor is M/S Rasuwa-Gajindra J/V with address Putalibazzar-1, Syangja, Contract signing Date 2071/02/12(26-May 2014), Date of Validity of Performance Security is 2071/02/11 (25-May-2014), 2073/08/25(7-May-2016), Date of Validity of Insurance 2073/01/28(10-May. 2016), Original Contract Amount NPR 76,318,182.39, % Below of Above (+/-) 0.42%, Contract amount after VO NPR 83,942,484.94, Original Intended Completion Date 18 months after, agreement date is 2072/08/10(26-Nov, 2015), Completion Date after EOT-1 is 2073/03/25(9-July, 2016), Completion Date after EoT-2 is 2073/12/18(31-March,2017), Completion Date after EoT-3 is 2074/02/06(20-May-2017), Completed date is 2074/02/14(28-May,2017) (DLP Certificate has been Issued).

## Technical Parameters

### Gradient

Normally hill rural road connect base point hill to top of hill or vice versa. So hill road requires frequent ascending and descending. For continuous rising or falling ruling gradient determine the rate of those

action. The maximum length of providing such gradient is normally limited to 150m as stated by Nepal Road Standard. The value of prescribed maximum gradient for feeder road is limited to 12% given by NRS 2070. Table 9 shows the observed value of maximum gradient at different section of road.

**Table-7: Observed Gradient in sampled section**

S.N	Sample section	Observed maximum gradient			Maximum Gradient as per NRS	Gradient +/- than standard gradient
		Chainage	Length	Measurement		
1	8+000 to 9+000	8+960 to 9+000	40	12%	12%	0%
2	9+000 to 10+000	9+240 to 9+300	60	11.5%	12%	-0.5%
		9+340 to 9+380	40	8.0%	12%	-4%
3	10+000 to 11+000	10+340 to 10+370	30	14.0%	12%	2%
4	11+000 to 12+000	11+340 to 11+420	80	10.4%	12%	-2%
		11+420 to 11+460	40	16.8%	12%	5%
		11+580 to 11+640	60	12.3%	12%	0%
		11+640 to 11+720	80	9.0%	12%	-3%
		11+720 to 11+780	60	8.2%	12%	-4%
		11+900 to 11+940	40	11.5%	12%	0%
5	12+000 to 13+000	12+260 to 12+340	80	15.6%	12%	4%
		12+360 to 12+400	40	6.0%	12%	-6%
		12+560 to 12+640	80	13.6%	12%	2%
6	13+000 to 14+000	13+140 to 13+200	60	12.8%	12%	1%
		13+460 to 13+520	60	13.0%	12%	1%
7	15+000 to 16+000	13+520 to 13+580	60	18.3%	12%	6%
		13+620 to 13+680	60	11.2%	12%	-1%
		15+300 to 15+360	60	14.8%	12%	3%
		15+520 to 15+560	40	14.3%	12%	2%
		15+940 to 16+000	60	17.5%	12%	6%
8	16+000 to 17+000	16+080 to 16+140	60	13.0%	12%	1%
		16+180 to 16+220	40	10.5%	12%	-2%
		16+240 to 16+360	120	15.2%	12%	3%
		16+420 to 16+500	80	17.6%	12%	6%
		16+540 to 16+620	80	11.4%	12%	-1%
		16+640 to 16+720	80	7.2%	12%	-5%
		16+860 to 16+920	60	13.0%	12%	1%
		16+960 to 17+040	80	18.8%	12%	7%
9	17+000 to 18+000	17+060 to 17+120	60	14.0%	12%	2%
		17+260 to 17+320	60	16.6%	12%	5%
		17+380 to 17+420	40	17.2%	12%	5%

Observed gradient at each kilometer measured shows that out of 31 section 10 (32.25%) section have gradient within the range i.e up to 12% (NRS 2070) and rest 21 (67.75%) section have gradient more than the maximum.

### Radius of horizontal curve

The vehicle length is related to the turning radius. Longer the vehicle length higher value of radius

is needed in turning. The horizontal alignment should be a smooth and as directed as possible while responsive to the topography. Table 10 shows the observed value of radius of horizontal curve at different section.

**Table-8: Curved radius in sampled section**

S. N	Chainage	Observed minimum radius		Minimum radius as per NRS(m)	Radius +/- than standard	Remarks
		Chainage	Measurement			
1	8+000 to 9+000	8+740	16.66	10	6.66	
2	9+000 to 10+000	9+180	7.42	10	-2.58	
		9+300	10.94	10	0.94	
		9+680	13.61	10	3.61	
		9+760	16.02	10	6.02	
		9+900	13.54	10	3.54	
3	10+000 to 11+000	10+320	7.47	10	-2.53	
4	11+000 to 12+000	11+300	13.09	10	3.09	
5	12+000 to 13+000	11+580	11.39	10	1.39	
		11+760	5.90	10	-4.10	
		11+960	5.25	10	-4.75	
		12+040	7.77	10	-2.23	
		12+260	14.50	10	4.50	
6	13+000 to 14+000	12+520	14.61	10	4.61	
		13+200	7.15	10	-2.85	
7	14+000 to 15+000	13+240	9.09	10	-0.91	
		14+040	16.27	10	6.27	
		14+620	12.44	10	2.44	
8	15+000 to 16+000	14+980	20.64	10	10.64	
		15+320	13.29	10	3.29	
9	16+000 to 17+000	15+860	12.33	10	2.33	
		16+300	12.96	10	2.96	
		16+460	9.30	10	-0.70	
10	17+000 to 18+000	16+860	7.70	10	-2.30	
		17+340	9.03	10	-0.97	
		17+480	6.80	10	-3.20	

Radius of curve 10m (NRS 2070) is the minimum radius when the design speed is 20kmph and maximum super elevation provided is 10%. From the study of 10 KM road at different 26 section 11 (42.3%) section was found smaller than the minimum requirement.

#### **Carriageway**

Width of the carriage way depends on the width of the traffic lane and number of lane. In a rural

road with feeder road standard, the minimum value of carriageway is 5.5 m i.e. intermediate lane. The carriageway in a curve section is greater than in straight section due to more space required in curve to turn front and rear part of vehicle. The carriage way with is 4.25 m in Badkhola-Takshar project. For the site verification, sample is taken at every 300m interval. Table 11 shows the observed carriage way width of the road.

**Table-9: Carriage way width in sample section:**

S.N	Sampled Chainage	Observed Carriageway (m)		Minimum carriageway as per design (m)	Carriageway +/- than standard
		Chainage	Measurement		
1	8+000 to 9+000	8+300	4	4.5	-0.5
		8+600	4	4.5	-0.5
		8+900	4.5	4.5	0
2	9+000 to 10+000	9+300	7	4.5	2.5
		9+600	4.5	4.5	0
		9+900	4.7	4.5	0.2
3	10+000 to 11+000	10+300	4.1	4.5	-0.4
		10+600	4.7	4.5	0.2
		10+900	5	4.5	0.5
4	11+000 to 12+000	11+300	6.5	4.5	2
		11+600	4.3	4.5	-0.2
		11+900	4.5	4.5	0
5	12+000 to 13+000	12+300	4.5	4.5	0
		12+600	5	4.5	0.5
		12+900	4.5	4.5	0
6	13+000 to 14+000	13+300	4.1	4.5	-0.4
		13+600	3.9	4.5	-0.6
		13+900	5.1	4.5	0.6
7	14+000 to 15+000	14+300	4.45	4.5	-0.05
		14+600	4.4	4.5	-0.1
		14+900	4.7	4.5	0.2
8	15+000 to 16+000	15+300	4.8	4.5	0.3
		15+600	4.5	4.5	0
		15+900	4.4	4.5	-0.1
9	16+000 to 17+000	16+300	5	4.5	0.5
		16+600	4.2	4.5	-0.3
		16+900	4.5	4.5	0
10	17+000 to 18+000	17+300	4.5	4.5	0
		17+600	4.5	4.5	0
		17+900	4.5	4.5	0

From the field verification it was observed that 10 (33.33% of total observed) section was found minimum carriage way width than standard.

### **Super Elevation**

Super elevation is provided in a horizontal curve. The normal value of super elevation provided is 7% as per NRS. NRS recommended on a hill road not

bound by snow a maximum super elevation up to 10 percent can be given. Minimum value of super elevation should be equal to the rate of camber of the pavement. Camber is 2.5% on bituminous, 4% on graveled and 5% on earthen surface as per NRS. The standard super elevation range is provided between 2.5% to 10% (NRS 2070) and compared accordingly which are given in following table.

**Table-10: Super elevation and its acceptance in sampled section:**

S.N	Sampled section	Observed super elevation		Super elevation range as per NRS	Acceptable (yes) or not acceptable (No)	Remarks
		Chainage	Measurement			
1	8+000 to 9+000	8+740	2.3%	2.5% to 10%	No	
2	9+000 to 10+000	9+180	1.8%	2.5% to 10%	No	
		9+300	2.8%	2.5% to 10%	Yes	
		9+680	3.8%	2.5% to 10%	Yes	
		9+760	3.3%	2.5% to 10%	Yes	
		9+900	2.1%	2.5% to 10%	No	
3	10+000 to 11+000	10+320	2.3%	2.5% to 10%	No	
		11+300	3.0%	2.5% to 10%	Yes	
	11+000 to 12+000	11+580	2.0%	2.5% to 10%	No	
4		11+760	2.4%	2.5% to 10%	No	
		11+960	2.2%	2.5% to 10%	No	
	12+000 to 13+000	12+040	1.8%	2.5% to 10%	No	
5		12+260	3.5%	2.5% to 10%	Yes	
		12+520	2.0%	2.5% to 10%	No	
6	13+000 to 14+000	13+200	2.7%	2.5% to 10%	Yes	
		13+240	1.1%	2.5% to 10%	No	
	14+000 to 15+000	14+040	2.0%	2.5% to 10%	No	
7		14+620	4.5%	2.5% to 10%	Yes	
		14+980	1.4%	2.5% to 10%	No	
8	15+000 to 16+000	15+320	4.2%	2.5% to 10%	Yes	
		15+860	2.0%	2.5% to 10%	No	
	16+000 to 17+000	16+300	2.0%	2.5% to 10%	No	
9		16+460	1.2%	2.5% to 10%	No	
		16+860	2.6%	2.5% to 10%	Yes	
	17+000 to 18+000	17+340	2.3%	2.5% to 10%	No	
10		17+480	1.9%	2.5% to 10%	No	

Data shows that only 9 (34.6%) section of observed road curve are found to be constructed and maintained with satisfactory super elevation range. Remaining 17(65.4%) section are not as per requirements.

#### Contract Procurement

Detail project report (DPR) was prepared by district technical office syangja and submitted to project

management unit (PMU) butwal for approval. DPR was approved on 2070/10/03. The approved cost of DPR was NPR 76,641,703. No objection letter (NOL) on bid documents was received on 2070/10/06. After NOL received procurement process was started. Detail of contract procurement of Badkhola-Takshar road was shown in table below.

**Table-11: Compliance status of Contract Procurements:**

SN	Description	Requirements	Compliance Status (Yes/No)	Date of Compliance	Remarks
1	<b>Contract Bidding</b>	1.1 Bid notices published date	Yes	13-10-70	
		1.2 Pre bid meeting	Yes	04-11-70	10 days before submission of bid
		1.3 Bid opening	Yes	14-11-70	30 days after Notice published
		1.4 Bid evaluation	Yes	04-01-71	Within 90 days after bid opening
2	<b>Contract Signing</b>	2.1 Contract Signing within 7 days of Letter of Acceptance	Yes	26-May-14	
		2.2 Work Order given for commencement of work within 15 days of contract signing date.	Yes	02-Jun-14	
3	<b>Performance Security</b>	2.1 Performance security submit before contract signing	Yes	25-May-14	
		2.2 Performance security Validity, DLP+30 days	Yes	10-Dec-16	
4	<b>Contract Start Date</b>	7 days after issuing work order	No	09-Jun-14	
5	<b>Possession of the Site</b>	15 Days after contract Start Date	No	24-Jun-14	
6	<b>Insurance</b>	<b>(a) for loss or damage to the Works, Plant and Materials:</b> Minimum cover: 115 % of the Contract amount. Maximum deductible: NRs.100, 000.00. <b>(b) For loss or damage to Equipment.</b> Minimum cover: NRs.2,000,000.00 Maximum deductible: NRs.25,000.00 <b>(c) For loss or damage to property</b> Minimum cover: NRs. 1,000,000.00 Maximum deductible: NRs.25,000.00 <b>(d) for personal injury or death:</b> (i) of the Contractor's employees: As per the Labour Act of Nepal. (ii) For Employers'/Engineers' staff: NRs. 500,000.00 (iii) of other people of third parties: NRs. 500,000.00	Yes	26-Jun-14	
7	<b>Advance Payments</b>				
7.1	<b>First Installment-5%</b>	After submission of Unconditional bank Guarantee	Yes	13-06-71	
7.2	<b>Second Installment-5%</b>	After submission of Unconditional bank Guarantee along with approval of joint construction survey, QAP, revised work schedule, full mobilisation of all key personnel, labor and equipment, insurance policies, establishment of labor camp and OSH provision.	Yes	17-08-71	

From the analysis of Procurement document, the procurement process was completed as per public procurement act 2064.

### Survey and design

The detailed engineering survey, design and cost estimate for upgrading of Badkhola-Takshar road has been prepared by District technical office syangja. The road alignment starts from 8+140 and end at 18+140.

Nepal rural road standard (2055) with second revision, DOLIDAR is followed to design the road. The

road falls under the category of district road core network as per NRRS as it connects village and district headquarters as well as SRN. Accordingly the design parameters and standards are considered for the road design. The total right of way adopted is 20m (10m on either side). Adopted roadway width is 4.25 which includes carriageway and shoulder, and formation width is 5.25 including drain.

After the agreement of contract joint construction survey was carried out by contractor with presence of client. Contractor prepared and approved the survey and design report from client.

Design of road was carried out by SW/DTM 2006 computer software developed by SOFTWEL (P) Ltd. Nepal and executes the Plan, Profile and Cross-section according to NRS 2070 which also gives the quantity of earthwork excavation, Quantity of retaining wall, crossing structure, quantity of sub-grade, sub-base and base. The approval of the design, drawing and quantity from client is 2071/03/10 (24-June, 2014).

## QUALITY OF WORKS

### (a) Quality of Structure

#### Masonry works

Requirements are, the masonry work shall be laid to lines, level, and dimensions as per approved design drawing; the stones shall be durable, angular, sound, hard, and free from iron cracks or other defects; the stone shall not absorb water more than 5 per cent. The specific gravity of the stone shall not be less than 2.50.; During construction, the Contractor shall make and test mortar cubes at the rate of three cubes for every 10m<sup>3</sup> of masonry to assess the strength subject to a minimum of 3 cubes samples for every day's work; At least 3 set of tests for stone and sand shall be conducted for every source.; The mortar used in work shall have the strength not less than 5 N/mm<sup>2</sup> or 7.5 N/mm<sup>2</sup> at 28 days as specified.

#### Findings

Total 1342.71 cubic meter masonry work was done in Badkhola-Takshar road. Among them 162 cum used for pipe culvert works, 628.45 cum for drain works, 408.49 cum for retaining wall and 143.77 cum for dry causeway works. From the observation it was found that masonry works was proper line and level. Material used (stone, cement and sand) was properly tested and approved. From the visual inspection no any defects were found in masonry structure. From the lab record data total 135 no of compressive strength test was done which meets the testing frequency as per specification. Test of Specific gravity and water absorption of stone, test of sand and cement meets the frequency requirements.

#### Gabion Works

Requirements are Stones used for filling the gabion boxes or mattresses shall be clean, hard, sound, un weathered and angular rock fragments or boulders. The length of any stone shall not exceed three times its thickness. The smallest dimension of any stone shall be at least twice that of the longer dimension of the mesh of the crate. All wires used in the manufacturing crates and diaphragms, binding and connecting lids and boxes shall be galvanized with an heavy coating of zinc by an electrolytic or hot dip galvanizing process. In walls, gabion boxes shall be placed such that vertical joints are not continuous, but staggered. Before filling with stone, gabions shall be anchored at one end or side and stretched from the opposite end or side by inserting temporary bars and levering them forward, The top

and bottom shall be kept stretched by tensioning with tie wires attached to an anchorage or equivalent approved method until the gabion has been filled.

The gabion wire shall be tested for mass, uniformity and adhesion of zinc coating and tensile strength of the wire.

#### Findings

983 Cubic Meter of gabion wall used at various chainage along the road was found. The line and level were maintained according to design drawing. No any defects were seen from the observation. Quarry of Stone used for the gabion was tested and approved. The specific gravity and water absorption was complying with the specification. Gabion wire used is machine made hexagonal mesh wire, complying with the NS 163-2045. Contractor submit sample of gabion boxes for necessary test. Two set of gabion wire test was done, from the test data it shows that adhesion of zinc coating and tensile strength was compliance with the specification.

#### Pipe Culvert

Requirements are, Reinforced concrete pipes shall comply with the requirements of NS 80/2042 or IS 458:1988. Trenches shall be kept free from water until the pipes are installed and the joints have hardened. The pipes shall be laid true to line and level, commencing from the outfall. Pipes shall be laid such that each one is in contact with the bed throughout the length of barrel. The pipes shall be laid closely together against each other so as to obtain tight joints. Catch pits, headwalls, wing walls, aprons and other ancillary works shall be constructed in accordance with the details shown on the Drawing. The Contractor shall submit manufacturer's test certificates for each lot of pipes supplied. The test results shall meet the requirements of the relevant Specifications.

#### Findings

Total 182 running meter pipe was used at various chainage along the road. 30 dia-15 no, 60 dia-127 no, 90 dia-40 no, each of 2.5m length reinforced concrete pipe was used. The pipe supplied meets the requirements of NS 80/2042. Bed of pipe was laid on layer of fine granular materials 100mm thick after bottom of the pipe was excavated and joints of pipe were done by cement mortar. The cover of pipe was provided 600mm over the crown of the culvert by suitable materials. Catch pits and headwall was done from stone masonry according to the drawing. In most places Outlet of the pipe was not provided suitable structure for proper water management. The Contractor submits manufacturer's test certificates for each lot of pipes supplied. The test results meet the requirements of the Specifications.

## Concrete works

Requirements are, Batching and mixing plants shall be complying with the requirements of IS 1791 and capable of producing a uniform distribution of the ingredients throughout the mass. Concrete shall be fully compacted throughout the full extent of the placed layer. It shall be thoroughly worked against the formwork and around any reinforcement and other embedded item, without displacing them. The test of Cement, sand, aggregate should be done before starts of works. Three sets of cube made for testing compressive strength of concrete for every 6 cum.

## Findings

978.2 cubic meter concrete class M15 was used for Drain PCC and Causeway works and 32.02 cum concrete class M10 was used for pipe culvert head wall and catch pit bed. From the record of lab it was observed that Materials use for concrete (cement, fine aggregate, coarse aggregate) were tested and approved from the lab. Total 204 no of compressive strength test was done from 1010 cum of concrete and 5 test was done for FI, LAA, and ACV.

### (b) Quality Assurance Plan (QAP)

QAP was prepared and submitted by contractor according to project format. The Contractor shall implement the Quality Control in compliance with the approved QAP.

Approved Quality assurance plan (QAP) was found and also revised QAP after variation order was submitted by contractor. The QAP shall include the following;

The Detail work procedure; Design drawing and specification; Organization chart with allocated role and responsibility; Work schedule; Material management schedule; Material testing schedule; Material extraction schedule for different sources; Spoil dumping location and Reinstatement of quarry site.

### (c) Construction methodology

Daily diary: Found partially compliance, few months maintain the works record on diary. Working Drawing: Not Compliance, No record was found of approval of working drawing before starts of work., Material stock record: No record was found; Labor record: No record was found; Accident Record: No record was found; Use of engineering instrument for line and layout of structure: Compliance and Used of level machine for line and layout.

### (d) Laboratory Operation

As per provision lab was established in DTO office syangja, all the test was done from this lab throughout the project. But the equipment is not sufficient for carryout all the test. The list of equipment's available in the lab is listed below.

The Lab test equipment's should be calibrated every year for obtaining accurate result; it was found that the all the machine was calibrated. The manpower is not sufficient for smooth operation of lab. There are one Lab in charge and one lab assistant, lab assistant must be 2 no and training for lab staff is not enough. There is provision of establishment of site laboratory by contractor. But no lab was established by contractor. All the lab operation was conducted from client lab. The test result was found properly recorded in file. From the test data it was found that the entire necessary test was conducted following the standard testing procedure. And test result shows that all the test of the material meets their requirement.

## Contract Management

It was observed that well contract management was adopted at the site.

## Financial Management

The Central Project Coordination Unit (CPCU) is responsible for overall budgeting. For each financial year the CPCU will prepare an annual budget indicating the activities to be carried out in the current financial year and the related budget, as well as the budget spent in the past financial year. District technical office (DTO) is responsible for Operate SNRTP Financial Transactions, Set up accounting system and maintain accounting records in accordance with requirements of the WB and the Government, submit Implementation Progress Reports (IPR) to the PMU; comprising Financial Management Reports (FMR) and Procurement Management Reports (PMR) on trimester basis within 15 (Fifteen) days from the end of trimester.

From the analysis of financial documents following activities were found. The first mobilization payment was made on date September 19, 2014 for amount NPR. 33, 51, 000 and second mobilization was made on December 03, 2014 for amount NPR 33, 51, 000. Mobilization was done after four months from the contract agreement. Nine running bill were made for the payment of works to the contractor on different date. No payment delay was found from the record. The Financial audit was done every year no Arrear (Beruju) Record was found from badkhola-Takshar road. Timely reporting to PMU and CPCU for the budget so that no budget scarcity during the contract period.

## Liquidity damage (LD)

Three (3) milestones had been kept in the contract for monitoring the progress of the works. The provision of liquidated damage had also been provided in the contract in case of not achieving these milestones on the scheduled date; with 0.005%, 0.025% and 0.05% of initial contract amount for 1st, 2nd and 3rd milestones respectively. Contractor was not able to achieve second and third revised milestone except first

milestone hence Liquidated damage for second and third milestone has been deducted in this contract.

#### Variation order (VO)

Due to the following major reason about 9.99 % variation order was issued to the contractor. Increase in width of roadway excavation and protection/check wall, water management works as per site condition reviewed in construction survey.

**Table-12: Summary of the variation Order**

Original Cost Estimate ( Including VAT)	Original Contract Amount ( Including VAT)	Revised Contract Amount (NRs) ( Including VAT)	Variation Amount (NRs) ( Including VAT)	Percentage Change in Contract Amount	Remarks
76,641,703.00	76,318,182.39	83,942,484.94	7,624,302.55	+9.99	

#### Extension of time (EOT)

In Badkhola-Takshar road three time extensions (541 days) were done due to following major reason are:

The Affected days due to 2072/01/12 (25-April-2015) Earthquake & its aftershock; Increase in quantity in earthwork in excavation in roadway; Strike and lack of fuel; Affected days due to fuel crises beyond 2073/08/11 (26-Nov-2016) and active monsoon, unfavourable time for otta-seal, national festival.

#### Monitoring, Supervision and reporting

Monitoring, supervision and reporting of Badkhola-Takshar road was found from the monthly progress report, site instruction record, and site visit record on Construction Site Monitoring (CSM)

Application. Continuous monitoring of works was from consultants where the project deploys technical, social and environment consultant for monitoring, supervision and reporting. For supervision works from contractor side only one sub-engineer handle the project most of the contract period. At the end of the project during pavement work one engineer recruit for supervision and monitoring but has less experience. Contractor mention his key personal (Contract manager-1, Site engineer-1, lab technician-1, sub engineer-1 and supervisor-3) in approved quality assurance plan (QAP) and contract documents also. But contractor has failed to comply monitoring and supervisory staff as per requirements.

#### Road safety and maintenance

In Badkhola-Takshar road following items of road safety works were performed.

**Table-13: Road safety works in Badkhola-Takshar Road**

S.N	Safety works	As per Contract (No)	Actual on site (No)	Remarks
1.	Traffic sign	30	28	
2.	Kilometer stone	9	9	
3.	5 Km stone	2	2	
4.	Delinator post	250	221	



**Fig-3: Installation of Traffic Sign and Delineator post**

Traffic Sign are provided to control and guide traffic and to promote road safety. Traffic signal should be properly installed along the road so as to ensure a

smooth flow of traffic as well as to caution the roads users about the possible hurdles and inconveniences.

Total cost allocation for road safety was NPR 5, 07, 000 which was only 0.7% of total estimated cost. So cost allocated for road safety works was not sufficient. The quantity estimate of traffic sign, delineator post was also not sufficient, from the field observation it was found that these are required in many

place. Road maintenance after the construction was found very poor. Road needs routine and recurrent maintenance. The surface deterioration rate is increase day by day; landslide from the slop blocked the drain in many place and water flow over the road.



Fig-4: Landslide blocked the drain

#### Analysis of Environmental parameters

The detail environmental cost and EMP implementation of Badkhola-Takshar road;

Table-14: Detail of EMP Implementation

S.N	Name of Road	Badkhola-Takshar
1	Major EMP Works	Bioengineering works, House Protection, Relocation, Drain management ,Labor camp Management,Occupational health and safety
2	EMP amount as per DPR , NPR	472,927.00
3	EMP cost as per Contract, NPR	298,200.00
4	EMP cost under user(LRUC), NPR	5,025,565.59
5	Total EMP cost, NPR	5,323,765.59
6	% of EMP cost against total contract	6.34%
7	<b>Paid EMP Amount</b>	
7.1	Contractor, NPR	1,31,313.00
7.2	LRUC, NPR	26,72,572.07

The environmental screening and Site-specific Environmental Management Plan (EMP) of Badkhola-Taksar-Dulegaunda Road was found and approved as provision in Environmental and Social Management Framework (ESMF). The environmental impact includes dust emission, noise pollution, use of bitumen, occupational health & safety, road safety measures. The impacts were minimized with the implementation of suggested measures forwarded by site- specific Environmental Management Plan.

#### Quarry site selection and management

Quarry site location as per EMP was at chainage 11+700 and 12+500. But contractor preferred road side cutting as quarry site. Materials were extracts from Quarry Chainage 11+700. But Quarry site management and restoration was not done. Slope

stabilization work, erosion control measure were not done as provision in ESMF.

#### Tipping site and its management

Following tipping site was identified for proper and safe disposal of soil.

Table-15: Tipping Site Location in EMP

Chainage	Land use	Area	Remarks
8+450	Barren Land	400	
9+500	Barren Land	400	
10+860	Jungle area	150	
12+550	Gulley	500	
13+920	Cultivated land	625	
16+900	Barren Land	650	

Adequate number of tipping site was not found because of hilly area. But above approved tipping site were also not fully utilized for soil disposal. Haphazard disposal of spoil were found without considering environmental impact. Spoil management plan (i.e Toe wall, shrub plantation, slope maintaining etc) were not done on tipping site.

#### Crusher site management

Crusher was established at CH: 12+600. Land agreement documents between contractor and concern stakeholder were found. Crusher site was located far from habitant area. Restatement of crusher site was not properly done. Crusher site was located near the road so vehicle movement was disturbed.

#### OSH and Labor camp

From analysis of site instruction, progress report, letter forwarded to contractor during construction period and consultation with stakeholders, the actual condition of OSH and labor camp on Badkhola-Takshar road was performed well.

#### Analysis of Social Parameters

The socio-economic condition is Moderate in Badkhola-Takshar road project area. Most of the people depend on agriculture. A few are engaged in the labor, services and small business activities. There are some small market centers in some part of the corridor. Brahman, Chhetri, Magar, Gurung and Dalit have occupied most of land. Summary of social safeguard implementation was attached in Annex -5.

#### Formation of Committee

Table-16: Committee formation

Level	Committees					
District Level	DRCC	GHC	ADC	LAC	DMC	OSH
Local Level	LRUC	VRCC				

As provision in ESMF, following committees were formed

#### Voluntary Donation Impact Mitigation Plan (VDIMP)

Table-17: Status of VDIMP

Road Name	Total Affected Plots	Total Affected Land (Sqm)	Assistance provided plots (in no.)	Ownership Transfer Completed (plot no.)	Total Assistance NRs. (Land+ Structure+Livelihood loss)
Badkhola-Takshar	159 nos	22215 Sqm.	159 nos	159 nos	Nrs.2,00,000

#### Social Management Plan

Social Management plan was prepared on the basis of 3% of total DPR cost.

Table-18: Status of Social Management Plan

Description of work	Documents Status	Budget	Training Provided	Remarks
VDIMP	Prepared	2,00,000.00	Assistance distribution to voluntarily land donors	Completed
VCDP	Prepared	2,89,545.47	Sewing & cutting, Beekeeping, Vegetable farming and House wiring training etc.	Yet not completed
GAP (Gender Action Plan)	Prepared	3 15,909.00	Sewing & cutting, Goat rising, Vegetable farming and Cardamom training etc.	Yet not completed

#### Monitoring and Supervision

As per the provision in ESMF following monitoring has been conducted in the road

Table-19: Monitoring and supervision status

Monitoring	As per provision	Conducted	Remarks
DMC (District Monitoring Committee) Monitoring	3	2	
Bi-Monthly Monitoring	12	7	
CBPM (Community Based Performance Monitoring)	3	2	

#### Compliance of social safeguard measures from contractor

From consultation with stakeholders, following condition was found.

**Table-20: Compliance of Social safeguard measures by Contractor**

S.N	Activities	Compliance	Non Compliance	Remarks
1	Use Construction material from approved site		Non Compliance	
2	Reclaim the quarry site and fill up borrow pit after the completion of the Work	Partially Compliance		
3	Keep the bitumen at least 1 Km far from the village/settlement	Compliance		
4	Maintain health and sanitation of the labor camp	Compliance		
5	Provide health and safety gears to the labors			
6	Keep records of periodic health checkup of labour		Non Compliance	
7	Do not allow haphazard disposal of spoil along hill slopes, vegetated areas, water bodies and other environmentally sensitive areas		Non Compliance	
8	Restrict labors' use of forest products, hunting and poaching	Compliance		
9	Avoid use of child labor (below 16 years age)	Compliance		
10	Employ as many women laborer as possible in construction		Non Compliance	
11	Contractors have to pay minimum wage fixed by the concerned district to both male and female labors.		Non Compliance	
12	Ensure life insurance of the laborers	Partially Compliance		
13	Relocate public infrastructure such as; electricity pole, telephone pole, taps, irrigation, etc	Compliance		

**Gaps and recommendation for future Improvement**

S.N	Gaps	Recommendation	Remarks
1.	Geometric design of the road was not as per design standards	Widening of curve section by cutting uphill side and/or inserting retaining wall in downhill side, replacing sharp curve with hair pin bends.	
2.	Contractor doesn't deploy his key personal (Contract manager, site engineer, lab technician) as mention in contract documents.	Don't pay the mobilization amount until the key personal present at site.	
3.	Contractor laboratory is not established at site		
4.	18 months project was completed in 36 months by extending project period into 3 times. Failure to complete project in time	Ask contractor for revised work program by increasing their manpower, material and equipment to complete the project into stipulated time frame.	
5.	OSH cost is not included in BOQ. So difficult to comply on site	provide 2-3% of total estimated cost for OSH and labor camp	
6.	Only 55% of environmental cost was completed. Reason is not performing the works by LRUC because of the profit motive.	Provision should be made to break the contract with LRUC and contract with other parties.	
7.	Land acquisition was taken just only formation width difficulties for further extension of width. And acquisition amount is only 5000 for land owner which is not sufficient.	At least right of way should be taken for land acquisition so that further intervention should be easy. Land acquisition amount should be increased and justified.	
8.	Maintenance of road after completion of works was not done due to which road deterioration was increased day by day, drain blockage in different section grass and bushes covered the drain and road surface.	Need of routine and recurrent maintenance immediately.	
9.	Quantity and cost estimated for safety management is not sufficient. Delineator post and traffic sign needed in different place. Safety barrier, safety reflector needed.	Sufficient budget allocated for Traffic safety management.	

**Construction site monitoring and reporting through CSM apps**

SNRTP developed CSM apps for supporting a comprehensive reporting system. It is envisioned that the system will have a central data repository and the districts will logged into the server for the data entry and generation of relevant reports. CSM is the Real time, location monitoring system, monitoring from mobile, based on GPS and Web, works in android platform devices.

The field visit report with photo/ videos is stored road wise and district wise in RuTIMS webpage. Any registered CSM user can view the auto generated report finalized by the recorder. It was useful for remote tracking of progress and quality of works. Even a general internet user can view the frequency of visits, overall status of CSM usage by users and districts




Fig-5: Sample of Uploaded CSM apps

### Orientation and Awareness program

District Technical office, syangja organized a campaign to improve the safety and health of workers and end child labour. The campaign aims to secure working environments for all workers and ending all forms of child from working site. Many factors can increase vulnerability to OSH risks, such as their physical and psychological stage of development, lack

of work experience and lack of training, limited awareness of work-related hazards and a lack of bargaining power that can lead workers to accept dangerous tasks or jobs with poor working conditions and safety. The program benefits to the labour about the importance and uses of safety tools and equipment, able to tackle with the minor accident and lowering the risk and basic training on first aid.



Fig-6: Awareness program on Occupational Safety and Health

### Project Performance Evaluation through Spider Chat

After Analysis of different parameters of the project, detail review of all these parameters was done from Expert (Client, consultant and Contractor) and score was given to each and every parameter. Separate sheet distributed to the expert where different parameters of the project are included and score range is specified from 0-10. From the average score spider charts was drawn which visualize performance of the project.

### CONCLUSION

Government of Nepal with support of World Bank implemented SNRTP project for strengthening rural road to bring the road to an all-weather maintainable standard. Badkhola-Takshar-Dulegaunda road was completed on 28<sup>th</sup> May 2018 on ottaseal standard. Strong supervision and monitoring

mechanism was established by the project to achieve standard quality works and success of the project. Assessment of the project represents evaluation of the project after its completion, analyzing the actual, as against the projected estimates in respect of time, cost and quality specifications.

The conclusion of the study based on the finding drawn from detail analysis of the project. These conclusions are followed by recommendation so as to address the compliance for maintaining the road parameters in the level of prescribed design standards for future project implementation. Compliance with geometric parameters was lagging in Badkhola-Takshar-Dulegaunda road. From the field observation at different section of the road, it was found that Road curve, gradient, super elevation, carriage way were not according to the prescribed design standard.

Traffic safety management of Badkhola-Takshar road project was found very poor due to low cost allocation. NPR 5, 000, 00.00 was allocated for 10 KM section. Traffic sign, delineator post installed in road is not sufficient. 25 no of traffic sign, 100 delineator post, 4 Safety reflector on sharp bends, and safety barriers on 3 places at stiff slop were required for proper safety management.

Foot path, street lights, waiting shed was not observed. Time overrun is the major issue of the project. The project was completed after 35 months as per mentioned in contract which was 18 months behind the original completion date. Road maintenance was found poor. The surface deterioration rate is increase day by day, landslide from the slop blocked the drain in many place and water flow over the road, vegetation from both side of the road cover the road surface. Monitoring, reporting, and evaluation were made effective by the use of Construction site monitoring (CSM) apps. This is the best part of the project.

Only 55% progress was achieved on allocated environmental budget. Contractor and LRUC failed to execute the environmental protection works such as tree plantation, slope protection, erosion control works etc. Partially compliance were found on environmental parameters, from the analysis of Tipping site management, Quarry site management, Bio-engineering works, Crusher site management. Occupational safety and Health (OSH) and labor camp management of Badkhola-Takshar road was found satisfactory, instead of allocating budget in BOQ.

Voluntary land donation from land owner was the great achievement of the project. Project existent was difficult without it; it is a great co-ordination between DTO, Project and local community. This project shows that development without local people participation would not sustainable until and unless people should feel the project constructed for their well-being. Bimonthly monitoring, Project monitoring from District monitoring committee (DMC) and Community based performance monitoring (CBPM) were not compliance as provision in ESMF. Provision for training provided for project affected people as per Vulnerable community development plan (VCDP) and Gender action plan (GAP) were not compliance.

## REFERENCE

1. SNRTP, ESMF. (2015). Environmental and Social Management Framework(ESMF)(Revised), Project for Strengthening the National Rural Transport Program (SNRTP), Available at <URL:<http://snrtp.gov.np/snrtp/wp-content/uploads/2016/07/Approved-ESMF-SNRTP.pdf>> [Accessed 5 August 2018]
2. DoLIDAR. (2016). Project Operations Manual (Version-2) Project for Strengthening the National Rural Transport Program (SNRTP), Available at < <http://snrtp.gov.np/snrtp/wp-content/uploads/2016/07/SNRTP-Revised-POM-Approved-on-14-April.pdf>> [Accessed on August 2, 2018]
3. DOLIDAR. (2017). "occupational safety and health guidelines" Available at < <http://snrtp.gov.np/snrtp/wp-content/uploads/2017/06/OSH-GUIDELINES.pdf> [Accessed on August 25, 2018]
4. Sharma, D. (2013). status paper on development of Asian Highway Routes Nepal, 2013, Fifth Meeting of the Working Group on the Asian Highway and Asian Highway Investment Forum Bangkok, Thailand, 7 to 9 October 2013, Available at < [https://www.unescap.org/sites/default/files/Nepal\\_1.pdf](https://www.unescap.org/sites/default/files/Nepal_1.pdf) -2-Oct-2018> [Accessed on October 2, 2018]
5. Thu, A.N., Visuth, C. (2013). A Practical list of criteria for evaluating construction project success in developing country, Available at < <http://seed-net.org/wp-content/uploads/2015/12/a-practical-list-of-criteria-for-evaluating-construction-project-success-in-developing-countries.pdf>> [assessed on 10<sup>th</sup> September 2018]
6. Karki, K., Poudel, P., Rothchild, J., Pope, N., Bobin, N. C., Gurung, Y., & Sherpa, L. (2017). Scoping review and preliminary mapping menstrual health and hygiene management in Nepal. *Lalitpur, Nepal: Population Services International Nepal*.
7. Tabish, S. Z. S., & Jha, K. N. (2011). Identification and evaluation of success factors for public construction projects. *Construction Management and Economics*, 29(8), 809-823.
8. Khosravi, S., & Afshari, H. (2011, July). A success measurement model for construction projects. In *International Conference on Financial Management and Economics IPEDR* (Vol. 11, pp. 186-190). IACSIT Press Singapore.
9. Al-Tmeemy, S. M. H. M., Abdul-Rahman, H., & Harun, Z. (2011). Future criteria for success of building projects in Malaysia. *International Journal of Project Management*, 29(3), 337-348.
10. Ahadzie, D. K., Proverbs, D. G., & Olomolaiye, P. O. (2008). Critical success criteria for mass house building projects in developing countries. *International Journal of project management*, 26(6), 675-687.
11. Menches, C. L., & Hanna, A. S. (2006). Quantitative measurement of successful performance from the project manager's perspective. *Journal of construction engineering and management*, 132(12), 1284-1293.
12. Bryde, D. J., & Robinson, L. (2005). Client versus contractor perspectives on project success criteria. *International Journal of project management*, 23(8), 622-629.
13. Lombard, S. M., & Kirchmer, C. J. (2004). *Guidelines for preparing quality assurance*

- project plans for environmental studies.* Environmental Assessment Program.
14. Halwatura, R. U., & Ranasinghe, N. P. N. P. (2013). Causes of variation orders in road construction projects in Sri Lanka. *ISR/N Construction Engineering*, 2013.
15. Trowers., & Hmlins, A. (2016). Projects and construction Liquidated damages in construction contracts in the Gulf, Available at <[https://www.trowers.com/uploads/Files/Liquidated\\_damages\\_in\\_construction\\_contracts\\_in\\_the\\_Gulf.pdf](https://www.trowers.com/uploads/Files/Liquidated_damages_in_construction_contracts_in_the_Gulf.pdf)> [assessed on 7<sup>th</sup> August 2018]
16. ADB, June. (2018). Price adjustment guidance note on procurement. Available at <<https://www.adb.org/sites/default/files/procurement-price-adjustment.pdf>> [assessed on 8<sup>th</sup> August 2018]
17. Damian McNair. (2016). Australia: Defects Liability Period: an Introduction International Best Practice in Project and Construction Agreements, <http://www.mondaq.com/australia/x/219302/Building+Construction/Defects+Liability+Period+an+Introduction>
18. DoLIDAR, February. (2018). Revised specification, SNRTP, Available at <[http://snrtp.gov.np/snrtp/wp-content/uploads/2018/02/Revised-Specification\\_February-06\\_2018.pdf](http://snrtp.gov.np/snrtp/wp-content/uploads/2018/02/Revised-Specification_February-06_2018.pdf)> [Accessed on August 25, 2018]
19. DOR, July. (2001). Standard specification for road and bridge, Available at <<http://dor.gov.np/home/publication/standard-specification-of-roads-and-bridges/standard-specifications-for-road-and-bridge-works-2-73>> [Accessed on August 10, 2018]